

Mobile Continuous Batching Plants



MOBIL
CON
TINUO
BATCHING
PLANTS



S.C.M.2

Impianti di Dosaggio e Betonaggio
Concrete Batching Plants
Centrales à Béton



These plants are suitable for low cement batching mixtures, like mortar or road subgrade.
Perfect control of batching through a detailed software with Personal Computer

- Equipped with continuous mixer
- Aggregate extraction takes place through volumetric belts whose flow is controlled by inverter
- The dosage of the cement is controlled by a system inverter for controlling the flow rate of the screw
- The dosage of the water is carried out with electromechanical flowmeter and proportional valve.
- The management system is fully automated by computer



Modello/Type/Modèle		TCM 100	TCM 150	TCM 200	TCM 300
Produzione oraria Hourly max. production Production Horarie max.	mc/h	100	150	200	300
Classe Inerti Aggregates Grades Classes agrégats	N°	2-3	3-4	3-4	4-5
Stoccaggio Inerti Aggregates storage Stockage agrégats	mc.	25	50 – 100	50 - 100	80 - 360



S.C.M. 2 S.r.l.

Impianti di dosaggio e betonaggio
Concrete batching plants
Centrales à béton

Via Pier Paolo Pasolini, 6 - 20845 SOVICO (MB)
Tel. +39 039 2323321-2016350 Fax +39 039 2323329
E.mail info@scm-impiani.it - www.scm-impiani.it